



Effect of Air Pollution on the Deterioration of El-Manial Palace and Museum for Greater Conservation of Egyptian Cultural Heritage



Asmaa El-Mekawy^{a*}, Abdel Hameed A. Awad^a, Alia Shakour^a, Inas A. Saleh^a, Yasser H. Ibrahim^a, Nasser M. Abdel-Latif^a and Salwa K. Hassan^a

^a Air Pollution Research Department, National Research Centre, Giza, Egypt

Abstract

Ancient archaeological buildings are witness on human civilization and cultures. Saving and conserving of cultural heritage is an urgent priority in Egypt and worldwide. El-Manial palace and museum is one of the most important Egyptian ancient archaeological buildings. It has a great historical and cultural value due to the presence of personal valuable property and memorabilia of Prince Mohammed Ali Tewfik objects. It is also reflecting the settings and lifestyle of the late 19th and early 20th centuries of Egyptian Royal Prince and their apparent. Unfortunately the palace is situated in a very crowded and polluted spot, so this study has been carried out for measuring the effect of surrounding pollutants on the palace building and monuments collections on it. RH%, temperature, particulate matter (PM) and its ionic species and gaseous air pollutants (sulphur dioxide, nitrogen dioxide, ammonia, hydrogen sulfide and formaldehyde) were measured inside and outside the museum. The annual mean concentrations of SPM in outdoor and reception hall exceeded both National and International limits. A/C ratios for all locations were greater than one, indicating that SPM were in acidic state, which had hazardous effect on the palace and its heritage constituents. Also, HCHO and NH₃ gases concentrations were high if compared with previous studies. Moreover, SO₂ and NO₂ gases were higher than international standards which form a critical negative impact on the palace.

Keywords: El-Manial palace and museum, PM, RH%, temperature, gaseous air pollutants, ionic air pollution, cultural heritage.

1. Introduction

In the last decades, indoor air pollution causes a global problem [1, 2]. The main source of indoor air pollutants is the outdoor air pollution; however indoor air pollutants may be of greater concern [3]. Moreover, indoor pollution in museums is one of the main causes of the cultural heritage deterioration and significantly influences the weathering of monuments and the deterioration of museum objects [4, 5]. The

assessment of air pollution in indoor cultural heritage buildings is a major concern for curators and conservators [6]. The conservation of typical collections is directly related to the indoor environmental conditions of the museums [7].

Airborne particulate matter (PM) is a complex mixture of organic and inorganic substances. It is made up of a number of components, including acids, organic chemicals, metals, and soil or dust particles

*Corresponding author: Asmaa M. El-Mekawy, E-mail: asmaamekawy75@gmail.com, Tel: +20 2 33371362).

Receive Date: 20 July 2020, Revise Date: 04 November 2020, Accept Date: 18 November 2020

DOI: 10.21608/EJCHEM.2020.34881.2755

©2021 National Information and Documentation Center (NIDOC)

[8]. Particulate matter is divided into two principal groups: coarse and fine particles, the smaller particles contain the secondarily formed aerosols. However, the larger particles usually contain earth crust materials and fugitive dust from roads and industries [9].

The deposition of particulate matter (PM) on monuments surfaces accelerates degradation, soiling, deterioration damages and disfiguration of objects (6, 10). The degree of damage happen depends on pollutant kind, its concentration, its chemical composition and particle size. Particulate matter can be indeed corrosive for its intrinsic nature, as for the presence of sodium chloride, or can act as carrier of more corrosive pollutants [11]. Damage can be intensified through the synergistic effects from air pollutants, temperature and/or humidity [12].

In the presence of humidity, NO₂ and SO₂ can be converted into nitric acid (HNO₃) and sulphuric acid (H₂SO₄), respectively. Acidic air pollution leads to hydrolytic degradation causing significant damage of the artifacts [13]. Formaldehyde (HCHO) is a major intermediate reaction product in atmospheric photochemistry. A major source of formaldehyde is incomplete combustion of hydrocarbon fuels, especially from vehicle emissions [14].

Hydrogen sulfide (H₂S) gas enters the environment from both natural and human processes [15]. The levels of hydrogen sulfide in air are typically low. Cairo is one of the most polluted cities in the world, in spite of the fact that it has a large number of archeological building, which represent a critical danger for these cultural heritages, so the aim of this study was to measure the most harmful pollutant indoor El-Manial Palace and museum and comparing the concentrations with local and international standards to evaluate the degree of danger this museum is subjected to for better conservation for this great cultural heritage.

2. Experimental:

2.1. Sampling site Description

El-Manial Palace was built by Prince Mohammed Ali Tewfik in year 1875. It was designed with an integrating European art style with remarkable traditional Islamic architecture. It housed his extensive art, furniture, clothing, silver, objects d'art

collections, and medieval manuscripts dating back to the middle Ages.

The palace and estate has been preserved as an Antiquities Council directed historic house museum and estate, reflecting the settings and lifestyle of the late 19th and early 20th century Egyptian royal prince. The residence compound, composed of five separate and distinctively styled buildings, is surrounded by Persian garden (~34000m) within an extensive English landscape garden, along a small branch of the Nile.

The five detached palace buildings formed the ensemble of El-Manial Palace where Turco-Islamic architecture prevailed (whether in the salamlik--reception quarters, the haramlik--main residence; the throne room, the golden hall or the palace mosque). The palace and museum is located in El-Manial district which is characterized by high traffic density, parking and located nearby the Cairo University and El-Qaser Eleyny hospital. Its coordinates are 30°01'39"N31°13'47"E.

In the present study indoor samples were collected from reception tower and residence palace only.




Figure (1): Map for El-Manial Palace and Museum



Figure (2): Prince's vintage butterfly collection

2.2. Air sampling and analysis:

The sampling was performed inside and outside of El-Manial palace and museum for a complete one year. The sampling was carried-out at two locations inside the museum. The description of the two sampling location are shown in Table (1). Field measurements and sampling were carried out at three sites, reception tower, residence palace and outdoor. Samples were taken at each sampling site during the working hours and routine daily activities in the period between 9 am and 4 pm, with 4 times every month. The samples were collected from fixed positions, at a height of ~ 1.5 m above the floor level at the center of the each building, and from 3-5 m outside the building to determine background level of air contamination. Sampling was carried out along one year from spring 2017 to winter 2018.

Microclimatic monitoring

Indoor/ outdoor temperature and relative humidity were measured using a portable weather instrument (SATO, PC- 5000 TRH-II sampler) at the time of sampling.

Determination of Suspended particulate matter

Suspended particulate matter (SPM) was collected through pre-weighted using Sartorius balance TE2145, Germany; and cellulose nitrate membrane filters (0.45 μm pore size and 47 mm diameter). The rate of sampling was 10 L/min. for 24 hour sampling occurred from 9.00 a.m. to 4.00 p.m. for three successive runs with three days a week. Filters were reweighted after sampling and difference in weight was SPM and expressed in $\mu\text{g}/\text{m}^3$.

Ion profile of suspended dust

The sampled dust filters were washed in 20 ml distilled water, shaken vigorously for 60 min and analyzed for water soluble ions, cations: Li^+ , Na^+ , NH_4^+ , K^+ , Mg^{2+} , and Ca^{2+} and anions: F^- , Cl^- , Br^- , NO_2^- , NO_3^- , PO_4^{3-} and SO_4^{2-} concentrations using ion chromatography (Dionex-ICS-1100, USA). The concentrations of soluble ions were expressed as (ng/m^3) of air.

Gaseous air pollutants

Sulphur dioxide (SO_2), nitrogen dioxide (NO_2), ammonia (NH_3), hydrogen sulfide (H_2S), and formaldehyde (HCHO) gases were measured according to previous studies [16 -20] using gas bubblers and vacuum pumps calibrated to draw air at flow rate of 1 L/min. The absorbance of the solution was measured by means of a UV-Visible spectrophotometer (Novaspec – LKB model 4049 – Biochrom, Cambridge, England), and concentration of gaseous air pollutant was expressed as $\mu\text{g}/\text{m}^3$.

2.3. Statistical analysis

Spearman's rank correlation test was used to determine relationships between suspended dust and gaseous air pollutants. A probability of less or equal to $P \leq 0.05$ was considered significant.

3. Results and discussion

3.1. RH% and Temperature measurements

Relative humidity (RH%) records were slightly higher in the residence and reception halls regarding to outdoor (Table 2). Relative humidity ranged within 44-54.5% in indoor air and 31.8-50.5% in outdoor air. Temperature records ranged between 13.6-28.7°C in indoor air and 13.2-31°C in outdoor air (Table 2). Microclimate conditions indoor and outdoor are closely similar, indicating the effect of outdoor weather conditions on indoors due to the absence of air conditions (artificial ventilation). The most acceptable temperature and RH% for the majority of archeological objects inside the museums is between 18 and 24°C, and between 40 and 55%, respectively, in order to avoid changing in the proportions of organic material [21], according to that temperature is considered high during summer season which form a hazard on the museum.

3.2. Suspended particulate matter (SPM)

SPM is complicated in composition, causing corrosion and soiling of exhibition materials. Vehicles are main sources of dust and smoke and their concentrations are influenced by daily activities, sampling site, nature of soil, plant cover and geographical characters in addition to ventilation type, occupancy load and household activities [22].

Fig 3 shows seasonal and annual average concentrations of SPM. The maximum seasonal concentrations of SPM were recorded in outdoor and reception hall air during autumn season (380.8 and 345.4 $\mu\text{g}/\text{m}^3$, respectively),

while the lowest concentration was in residence hall during spring season ($35\mu\text{g}/\text{m}^3$).




Figure 3: Seasonal variation and annual average concentrations of SPM at different locations of the museum

I/O ratios of SPM concentrations for reception hall exceeded 1 during winter season, which indicates that indoor pollutants play a major role in reception hall air pollution. I/O ratios of SPM concentrations for residence hall did not exceed 1 during other seasons, indicating that outdoor environment was the main source of SPM.

The maximum annual mean concentration recorded in outdoor followed by reception hall ($223.4\mu\text{g}/\text{m}^3$ and $220.4\mu\text{g}/\text{m}^3$, respectively), while the minimum annual concentration recorded in residence hall $92.8\mu\text{g}/\text{m}^3$. In the present study SPM concentrations exceeded the limit values set by the EPA, museum US National Bureau of Standards and The Kuwait EPA ($75\mu\text{g}/\text{m}^3$) [23-25], the Egyptian ambient air quality standard ($125\mu\text{g}/\text{m}^3$) [26], WHO range ($60-90\mu\text{g}/\text{m}^3$) [27], the Malaysian National Standard and the Australian NHMRC ($90\mu\text{g}/\text{m}^3$) [24, 28], and much higher than concentration found by El-Mekawy et al. in indoor air of Sohag university museum ($52.3\mu\text{g}/\text{m}^3$) [29]. High SPM concentrations in the museum can cause a significant change in the colour and in the physical properties of the coating layer of the oil painting present in the museum which can cause small holes on the surface of the oil paintings [30].

The high concentration of SPM inside the reception hall is attributed to its location nearby the crowded road and traffic area, so it is affected by emissions from outdoor. Outdoor environment is characterized by heavy traffic, other anthropogenic activities, and the museum is located nearby the Cairo University. Significant correlation was found between SPM concentrations outside and inside the reception hall ($p \leq 0.01$) and non-significant correlation was found

between SPM concentrations outside and inside residence hall ($P \geq 0.05$), respectively.

3.3. SPM Soluble ions profile

3.3.1. Anions

Figure (4) illustrates anion concentration in each site under investigation. As clear from this figure, the maximum concentration for all anions (except PO_4^{3-}) in outdoor air was during autumn season. NO_3^- anion was the most abundant anion in outdoor air ranged from $82.2\text{ng}/\text{m}^3$ in autumn to $14.2\text{ng}/\text{m}^3$ in spring. On the other hand, Br^- was the least abundant anion in outdoor air, ranged from $0.041\text{ng}/\text{m}^3$, in autumn, to $0.022\text{ng}/\text{m}^3$ in summer. Furthermore, spring season was the most rich season in anions in both reception and residence halls. NO_3^- anion was the most abundant anion in reception hall ranged from $110.5\text{ng}/\text{m}^3$ during spring to $23.8\text{ng}/\text{m}^3$ during summer with mean concentration of $60.27\text{ng}/\text{m}^3$, while SO_4^{2-} was the most common anion in residence hall ranged from $66.2\text{ng}/\text{m}^3$ during spring to $9.08\text{ng}/\text{m}^3$ during autumn with mean concentration of $33.4\text{ng}/\text{m}^3$. Br^- anion formed the least SPM constituent in both reception and residence halls ranged from $0.047\text{ng}/\text{m}^3$ during autumn to $0.039\text{ng}/\text{m}^3$ during summer (with mean concentration of $0.044\text{ng}/\text{m}^3$) in reception hall and from $0.031\text{ng}/\text{m}^3$ during spring to $0.002\text{ng}/\text{m}^3$ during summer (with mean concentration of $0.017\text{ng}/\text{m}^3$) in residence hall.




Figure 4: Anion concentration at each site under investigation

Figure (5) shows mean anion concentration in the investigated locations. Reception hall had the greatest anion constituent comparing to other sites followed by outdoor, while residence hall recorded the least anion concentration. I/O ratios for reception anions were greater than 1 for most anions (Figure 6) which indicates that this site is affected by both indoor and outdoor air pollutants; meanwhile I/O ratios for residence hall were less than 1 for all anions except for Cl^- and SO_4^{2-} anions.




Figure (5): mean anion concentration at investigated sites




Figure (6): I/O ratios of anions in reception and residence halls

3.3.2. Cations

Cations concentrations in investigated sites are illustrated in Figure (7), which shows that Li^+ cation was under detection limit in all sites. Maximum cations concentrations in outdoor were detected during autumn season, while in reception and residence halls were detected during spring season (except Mg^{2+} and Ca^{2+} in reception were during autumn). The most abundant cations in outdoor were Na (ranged from 34.8 ng/m³ during autumn to 8.33ng/m³ during spring with mean concentration 17.6 ng/m³) and Ca^{2+} (ranged from 36.3 ng/m³ during autumn to 9.4 ng/m³ during spring with mean concentration 19.2ng/m³). On the other hand, the most abundant cations in both reception and residence halls were NH_4^+ (ranged from 81.7 ng/m³ during spring to 4.8 ng/m³ during summer with mean concentration 33.1 $\mu\text{g}/\text{m}^3$ in reception hall and from 23.1 ng/m³ during spring to 2.7 ng/m³ during autumn with mean concentration 10.3 ng/m³ in residence hall) and Ca_2^+ (ranged from 60.9 ng/m³ during autumn to 12.2 ng/m³

during summer with mean concentration 31.1 ng/m³ in reception hall and from 56.04 ng/m³ during spring to 4.27 ng/m³ during autumn with mean concentration 23.1 ng/m³ in residence hall). The least abundant cation in all investigated sites was Mg^{2+} (mean concentration 3.3, 3.3 and 5.06 ng/m³ in outdoor, reception and residence halls, respectively).




Figure 7: Cations concentration in locations under investigation

Reception hall had the greatest cation concentration comparing to other sites followed by residence then outdoor (as seen from figure 8). I/O ratios for cations in both reception and residence halls were greater than or near 1 for most cations (as shown in Figure 9) which indicates that these locations are affected by both indoor and outdoor air pollutants in contamination with cations.




Figure (8): mean cations concentration in investigated sites




Figure (9): I/O ratios of cations in reception and residence halls

Acidity of SPM

The acidity of SPM is an important factor that affecting the reactions of SPM with surrounding objects [31,32]. To evaluate the acid-base balance of SPM the ratios of anion (A) and cation (C) microequivalents are calculated. A/C ratio greater than 1 indicates that particle is in acidic. Particles in ionic equilibrium state when the A/C ratio be close to 1 [33,34].

A/C ratios for all under investigation locations exceeded one (Table 3), indicating that SPM were in acidic state, which could cause deterioration and corrosion of works of art inside museum.

3.4. Gaseous pollutants

Figure (10) shows the seasonal mean concentrations of the gaseous pollutants in sites under investigation in El-Manial museum. The most common gas in the reception hall and residence hall was HCHO gas followed by NH_3 gas; while the least gas concentration was for H_2S gas. On the most abundant gas in outdoor air was NH_3 gas followed by HCHO gas. The maximum HCHO concentrations (236.8 and 205.4 $\mu\text{g}/\text{m}^3$) were recorded during spring in outdoor air and reception hall air, respectively. On the other hand the minimum HCHO concentration (38.7 $\mu\text{g}/\text{m}^3$) was found in outdoor air during summer season.

The maximum concentrations of NH_3 were recorded during winter season in all sites under investigation, while the minimum concentrations were recorded during spring season. H_2S was the least abundant gas in air of investigated sites. The maximum H_2S seasonal concentration 21.6 $\mu\text{g}/\text{m}^3$ was recorded during spring in reception hall air, while the minimum seasonal concentration was 0.019 $\mu\text{g}/\text{m}^3$ in residence hall air during spring season. The maximum seasonal concentrations of both NO_2 and SO_2 gases were during winter season, while least concentrations were during summer season.

The highest annual mean concentration of gases in air of studied sites was NH_3 gas followed by HCHO and

NO_2 gases (Figure 11). On the other hand, the less abundant gas was H_2S gas. The highest gas concentration was recorded for HCHO gas in reception (126.1 $\mu\text{g}/\text{m}^3$) followed by NH_3 gas in reception too (116.06 $\mu\text{g}/\text{m}^3$). High HCHO gas concentration may be attributed to the location of this hall, which is located on the road, so it is affected by both outdoor and indoor pollution. This hall is characterized by the presence of several old stuffed and surrounding vegetation, renovation, and inadequate ventilation [35]. Formaldehyde is identified as a danger to museum collections [36]. Pavlogeorgatos [36] observed elevated concentrations of formaldehyde in Zoological Museum.

HCHO gas was high in outdoor air too. High concentration of HCHO in outdoor air may be attributed to the location of the museum near highly traffic road and the presence of AlQasr AlAyini hospital which is characterized by the presence of its incinerator, as boilers and incinerators consider a main source of HCHO in air [14, 37]. Annual mean concentrations of HCHO in reception and outdoor air are higher than limit values set in Canada 50 $\mu\text{g}/\text{m}^3$ 8 hour average and 60 $\mu\text{g}/\text{m}^3$ as a ceiling limit value for long-term exposure [38, 39], and in Sweden and Poland 100 $\mu\text{g}/\text{m}^3$ [40, 41].




Figure (10): seasonal mean concentrations of gases in the different investigated sites




Figure (11): annual mean concentration of investigated gases

SO₂ concentrations were lower than NO₂ concentrations in most of sites under investigation, due to decline in fuel oil use and reduction in the sulphur content of gas oil and diesel fuel. In locations such as busy roads nitrogen dioxide concentrations are relatively high. In museum environment it is very difficult to decide at what level a pollutant becomes a threat. This is because of the prolonged exposure period, which may be detected in decades and over a time span, even quite low concentrations may be dangerous. Thomson [42] suggested that sulphur and nitrogen dioxides concentrations should not exceed 10 µg/m³. The US National Bureau of Standards has made even more stringent recommendations of less than 1 µg/m³ sulphur dioxide and less than 5 µg/m³ nitrogen dioxide for archival storage conditions [43], the EU and WHO set value 40 µg/m³ for NO₂ gas in air and 20 µg/m³ for SO₂ gas [44, 45]. SO₂ and NO₂ annual mean concentrations exceeded 35 µg/m³ and 53 µg/m³ at outdoor and reception hall, respectively. NO_x primarily emitted by motor vehicle and stationary combustion sources, and NH₃ primarily emitted by agricultural operations. In the present study NO₂ and SO₂ concentrations exceeded the previously mentioned limit values. Sulfur dioxide (SO₂) and nitrous oxide (NO₂) have great effects on cultural heritages (buildings, marble, limestone, tuff and sandstone) due to the formation of acid rains which dissolves the surface increasing weathering of materials and can even destruct the object itself [46]. Ingo [11] attributed corrosion phenomena on alloy surface, in an Egyptian museum, to sulphur and chlorine that react in different ways, depending on the exhibition conditions.

The concentration of NO₂ is usually high in an urban atmosphere, due to its emission by automobiles [6].

I/O ratio of gaseous pollutants

The annual indoor /outdoor ratios of gaseous pollutants are shown in figure (12). I/O ratios of NH₃ and H₂S were

≥ 1 at indoor locations, and HCHO only in reception hall, confirming the presence of internal sources of these gaseous pollutants. I/O ratios confirmed that outdoor sources are the main sources of SO₂ and NO₂ indoor. I/O ratio of HCHO exceeded 1 at the reception hall, less than 1 at the residence, indicating that HCHO has indoor and outdoor sources. Variations of I/O ratios indicate outdoor free air movement at different locations.




Figure (12): Annual I/O ratios of gaseous pollutants

There were strong correlation between outdoor and residence HCHO (as seen from table 4), also there were strong correlation between outdoor NH₃ and NH₃ in both residence and reception halls, and between outdoor (SO₂ and NO₂) and SO₂ and NO₂ in both residence and reception halls.

There was a strong correlation between NH₃ and H₂S and between SO₂ and NO₂ gases in outdoor air (table 5 (A)), and strong correlation between H₂S and both HCHO and NH₃ and between SO₂ and NO₂ in both residence and reception halls (table 6 (B and C)).

4. Conclusions

For better preservation of cultural heritage, special attention should be paid to the air pollutants and its constituents. The study showed that temperature records were slightly high. PM concentrations were higher than the national and international limit values. A/C ratios were greater than one, indicating that PM were in acidic state which have great effect on art exhibits inside museums.

Reception hall had the greatest anion and cations constituents comparing to other sites. NH₄⁺ was the most abundant cation. HCHO was the most abundant gas in the air inside the museum. NO₂ and SO₂ concentrations exceeded the US National Bureau of Standards limit values. I/O ratios of SO₂ and NO₂ gases confirmed that outdoor sources are the main source for them in indoor air. Natural ventilation is very dangerous to the museum's objects and exhibits.

5. Conflict of interest

The authors have no actual or potential conflict of interest including any financial, personal or other relationships with other people or organizations within three years of beginning the submitted work that could inappropriately influence, or be perceived to influence, their work.

6. Funding

This work was supported by the National Research centre (Giza, Egypt) [under the grant number 11070108]

5. Acknowledgment

The authors are grateful to National Research Centre (Giza, Egypt), for supporting this work

Table (1): description of sampling sites

| Location | Description | Ventilation type |
|------------------|--|------------------|
| Reception tower | It consists of two floors, each floor comprising of two halls. Its purpose was to receive official guests and contains rare antiques including carpets and Arabian furniture and tables. It is located near the crowded street. | natural |
| Residence palace | It was dedicated to residence of the prince, it consists of two floors; the ground floor consists of the reception and dining rooms, prince's office and library, whereas the upper floor was for bed rooms. It is located far from street and surrounded by big garden. It is located away from road. | natural |

Table (2): Relative Humidity (RH %) and Temperature°C outside and inside the museum halls

| | Relative Humidity (RH %) | | | Temperature°C | | |
|----------------|--------------------------|-----------|-----------|---------------|-----------|-----------|
| | Outdoor | Reception | Residence | Outdoor | Reception | Residence |
| Spring | 31.8 | 44 | 49.6 | 26 | 19.2 | 18.4 |
| Summer | 35 | 45 | 54.5 | 31 | 28.7 | 27.2 |
| Autumn | 50.5 | 51.2 | 53 | 19.2 | 19 | 19.3 |
| Winter | 49.6 | 48.8 | 51 | 13.2 | 14.1 | 13.6 |
| Annual average | 41.7 | 47.2 | 52 | 22.3 | 20.2 | 19.6 |
| S.D. | 9.6 | 3.3 | 2.1 | 7.7 | 6.1 | 5.6 |
| Max | 50.5 | 51.2 | 54.5 | 31 | 28.7 | 27.2 |
| Min | 31.8 | 44 | 49.6 | 13.2 | 14.1 | 13.6 |

Table (3): Anions (A) and cations (C)microequivalents and there ratios

| | \sum anions ng/m ³ | \sum cations ng/m ³ | A/C |
|-----------|---------------------------------|----------------------------------|-----|
| Outdoor | 122.03 | 55.53 | 2.1 |
| Reception | 155.06 | 97.03 | 1.5 |
| Residence | 75.97 | 58.47 | 1.2 |

Table (4): Correlation between gases in outdoor air and both Residence and Reception halls.

| | | Outdoor | | | | |
|-----------|------------------|-------------|-----------------|------------------|-----------------|-----------------|
| | | HCHO | NH ₃ | H ₂ S | NO ₂ | SO ₂ |
| Residence | HCHO | 0.92 | -0.37 | -0.51 | -0.35 | -0.46 |
| | NH ₃ | -0.51 | 0.93 | 0.90 | 0.14 | 0.17 |
| | H ₂ S | -0.62 | 0.85 | 0.85 | 0.25 | 0.29 |
| | NO ₂ | -0.21 | -0.26 | -0.32 | 0.94 | 0.96 |
| | SO ₂ | -0.12 | -0.22 | -0.28 | 0.95 | 0.97 |
| Reception | HCHO | 0.56 | -0.86 | -0.92 | 0.33 | 0.29 |
| | NH ₃ | -0.43 | 0.93 | 0.87 | 0.23 | 0.25 |
| | H ₂ S | 0.90 | -0.60 | -0.72 | -0.14 | -0.24 |
| | NO ₂ | -0.09 | -0.19 | -0.26 | 0.96 | 0.97 |
| | SO ₂ | 0.04 | 0.11 | -0.05 | 0.96 | 0.94 |

Table (5): Correlation between gases in each site ((A) outdoor air, (B) Reception hall and (C) Residence hall)

| | HCHO | NH ₃ | H ₂ S | NO ₂ |
|------------------|--------------|-----------------|------------------|-----------------|
| NH ₃ | -0.23 | | | |
| H ₂ S | -0.45 | 0.87 | | |
| NO ₂ | -0.03 | -0.03 | -0.09 | |
| SO ₂ | -0.16 | -0.04 | -0.07 | 0.98 |
| (A) | | | | |
| | HCHO | NH ₃ | H ₂ S | NO ₂ |
| NH ₃ | -0.81 | | | |
| H ₂ S | 0.76 | -0.78 | | |
| NO ₂ | 0.44 | 0.09 | -0.12 | |
| SO ₂ | 0.26 | 0.34 | -0.14 | 0.92 |
| (B) | | | | |
| | HCHO | NH ₃ | H ₂ S | NO ₂ |
| NH ₃ | -0.66 | | | |
| H ₂ S | -0.79 | 0.98 | | |
| NO ₂ | -0.36 | -0.05 | 0.08 | |
| SO ₂ | -0.39 | -0.007 | 0.13 | 0.99 |
| (C) | | | | |

References

- [1] Andrade A., Dominski F.-H. (2018) Indoor air quality of environments used for physical exercise and sports practice: systematic review. *J. Environ. Manag.*, 206, 577–586.
- [2] Du, W., Li, X., Chen, Y., Shen, G. (2018) Household air pollution and personal exposure to air pollutants in rural China - a review. *Environ. Pollut.*, 237, 625–638.
- [3] Morawska, L., Ayoko, G.A., Bae, G.N., Buonanno, G., Chao, C.Y.H., Clifford, S., Fu, S.C., Hanninen, O., He, C., Isaxon, C., Mazaheri, M., Salthammer, T., Waring, M.S., Wierzbicka, A. (2017) Airborne particles in indoor environment of homes, schools, offices and aged care facilities. The main routes of exposure. *Environmental international*, 108, 75:83.
- [4] Marchetti, A., Pilehvar, S., Hart, L., Pernia, D.L., Voet, O., Anaf, W., Nuyts, G., Otten, E., Demeyer,

- S., Schalm, O., De Wael, K. (2017) Indoor environmental quality index for conservation environments: the importance of including particulate matter, *Building and Environment*, 126: 132–146.
- [5] Martinez-Molina, A., Boarin, P., Tort-Ausina, I., Vivancos, J.-L. (2018) Assessing visitors' thermal comfort in historic museum buildings: results from a post-occupancy evaluation on a case study, *Building and Environment*, 132, 291–302.
- [6] Godoi, R.H.M., Carneiro, B.H.B., Paralovo, S.L., Campos, V.P., Tavares, T.M., Evangelista, H., Van Grieken, R., Godoi, A.F.L.(2013) Indoor air quality of a museum in a subtropical climate: The Oscar Niemeyer museum in Curitiba, Brazil. *Science of the Total Environment*, 452–453: 314–320.
- [7] Lankester, P., Brimblecombe, P. (2012) The impact of future climate on historic interiors. *Science of the Total Environment*, 417–418:248–54.
- [8] CalEPA (California Environmental Protection Agency) (1999) Air Resources Board Toxic Air Contaminant Summary Hydrogen sulfide.
- [9] Hanapi, N., Mohd Din, S.A. (2012) A Study on the Airborne Particulates Matter in Selected Museums of Peninsular Malaysia, *Procedia - Social and Behavioral Sciences*, 50, 602 – 613
- [10] Krupińska, B., Worobiec, A., Rotondo, G.G., Novaković, V., Kontozova, V., Ro, C., Grieken, R.V., De Wael, K. (2012) Assessment of the air quality (NO₂, SO₂, O₃ and particulate matter) in the Plantin-Moretus Museum/Print Room in Antwerp, Belgium, in different seasons of the year. *Microchemical Journal*, 102, 49–53
- [11] Ingo, G.M., Angelini, E., Riccuccia, C., de Caroa, T., Mezzia, A., Faraldib, F., Cascheraa, D., Giuliana, C., Di Carola, G. (2015) Indoor environmental corrosion of Ag-based alloys in the Egyptian Museum (Cairo, Egypt), *Applied Surface Science*, 326 (2015) 222–235.
- [12] Camuffo, D. (1988) *Microclimate for Cultural Heritage*. Elsevier, Amsterdam, 1998.
- [13] Vallero, D. (2008) *Fundamentals of Air Pollution*, fourth ed. Academic Press, Oxford.
- [14] Pohanish, R.P. (2002) *Sitting's Handbook of Toxic and Hazardous Chemicals and Carcinogens*, 4th Ed., Norwich, NY, Noyes Publications/William Andrew Publishing, pp. 1179–1182.
- [15] CAI-Asia Center (2010) *Particulate Matter (PM) Standards in Asia*. Retrieved from www.cleanairinitiative.com.
- [16] West, P.W., Gaeke, G.C.(1986) *Analytical Chemistry*, 28, 1916. In Stern, A.C. 1968, 2nd, Vol II, Acad. Press New York.
- [17] CPCB (Central Pollution Control Board) (2011) *Guidelines for the measurement of ambient air pollutants: Volume-I*, New Delhi, India.
- [18] Marr, L.M., Cresser, M.S. (1983) *Environmental chemical analysis*. Inter. Textbook Company Chapman and Hall, N.Y. pp. 122-126.
- [19] Perry, R., Young, R.J. (1977) *Handbook of air pollution analysis*, Eds, Chapman and Hall, London.
- [20] Harrison, R.M., Perry, R. (1986) *Handbook of air pollution analysis*, Chapman and Hall, London, New York, 2nd edn.
- [21] Zorpas, A. A., Skouroupatis, A. (2016) Indoor air quality evaluation of two museums in a subtropical climate conditions. *Sustainable Cities and Society*, 20, 52:60.
- [22] Meadow, J.F., Altrichter, A. E., Kembel, S.W., Moriyama, M., Connor, T.K.O., Womack, A.M., Brown, G.Z., Green, J.L., Bohannan, B.J.M. (2014) Bacterial communities on classroom surfaces vary with human contact. *Microbiome*, 2, 7:15.
- [23] USEPA (U.S. Environmental Protection Agency) (1974) *Air quality criteria for Suspended Particulate*.
- [24] DOE (2006) *Malaysia Environmental Quality Report*. Department of Environment, Ministry of Natural Resources and Environmental Malaysia.
- [25] Tang, H., AlAjmi, D. (2005) *Introduction to Air Pollution and Air Quality Management*, Environment and Urban Development Division Kuwait Institute for Scientific Research, <http://www.kisr.edu.kw/pubs/en/books/99906-41-50-1.pdf>, accessed in May 2015
- [26] EEAA (2012) *Egyptian Environmental Affair Agency. State of Environment Report 2012*
- [27] WHO (World Health Organization) (1979) *Sulfur oxides and suspended particulate matter, Environmental Health Criteria*, 8, Geneva.
- [28] TEC Green Office (1997) *Indoor Air Quality Guidelines for Sydney Olympic Facilities*, Sydney, Australia.
- [29] El-Mekawy, A., Shakour, A. Elryan, R. and Hassanein, B. (2020) *Air Quality inside Faculty of Art Museum of Sohag University*. International

- Journal of Advanced Science and Technology, 29; 3, 8200 – 8208.
- [30] Abatable, Th. and El-Mekawy, A. (2019) An Applied Study of the Effect of Air Pollution on Non-Environmentally Friendly Colors of Archaeological Oil Paintings In The Vicinity of the Nubia Museum in Aswan. International Journal of Advanced Science and Technology, 28; 16, 747 – 762.
- [31] Sun, J., Zhang, Q., Canagaratna, M.R., Zhang, Y., Sun, Y., Jayne, J.T., Zhang, X., Zhang, X., Worsnop, D.R. (2010) Highly time- and size-resolved characterization of submicron aerosol particles in Beijing using an Aerodyne Aerosol Mass Spectrometer. Atmospheric Environment, 44, 131:140.
- [32] Cheng, H.R., Gong, W., Wang, Z.W., Zhong, F., Wang, X.M., Lv, X.P., Liv, J., Fu, X.X., Zhang, G. (2014) Ionic composition of submicron particles (PM₁₀) during the long-lasting haze period in January 2013 in Wuhan, Central China. Journal of Environmental Science, 26, 810-817.
- [33] Wang, Q., Cao, J., Shen, Z.X., Tao, J., Xiao, S., Luo, L., He, Q.Y., Tang, X. (2013): Chemical characteristics of PM_{2.5} during dust storms and air pollution events in Chengdu, China. Particuology, 11, 70:77.
- [34] Gao, J., Tian, H., Cheng, K., Lu, L., Zheng, M., Wang, S., Hao, J., Wang, K., Hua, S., Zhu, C., Wang, Y. (2015) The variation of chemical characteristics of PM_{2.5} and PM₁₀ and formation causes during two haze pollution events in urban Beijing, China. Atmos. Environ. 107, 1-8.
- [35] WHO (WHO, World Health Organization) (2000) Air quality guidelines for Europe, World Health Organization Regional Office for Europe, Copenhagen: (http://www.euro.who.int/__data/assets/pdf_file/0005/74732/E71922.pdf) (accessed on 9 July 2018).
- [36] Pavlogeorgatos, G. (2003) Environmental parameters in museums, Building and Environment, 38, 1457–1462.
- [37] WHO (World Health Organization) (1989) Indoor air quality: organic pollutants. WHO Regional Office for Europe (EURO Reports and Studies No. 111), Copenhagen.
- [38] ANSI/ASHRAE, (2004) Ventilation for Acceptable Indoor Air Quality, American Society of Heating, Refrigerating and Air-Conditioning Engineers, INC, 1791 Tullie Circle NE, Atlanta, GA 30329, http://isites.harvard.edu/fs/docs/icb.topic256760.files/62_1_2004.pdf, accessed in May 2015.
- [39] Dales, R., Liu, L., Wheeler, A.J., Gilbert, N.L. (2008) Public health: Quality of indoor residential air and health. CMAJ, 179, 147–152.
- [40] Salthammer, T., Mentese, S., Marutzky, R., (2010) Formaldehyde in the indoor environment. Chemical Reviews, 110, 2536–2572.
- [41] NRC (National Research Council Canada) (2005) Managing Volatile Organic Compounds and Indoor Air Quality in Office Buildings: An Engineering Approach, RR205, Consortium for Material Emissions and Indoor Air Quality Modeling II (CMEIAQ-II), Report 5.2.
- [42] Thomson G. (1986) The Museum Environment', 2nd edition, London: Butterworths. National Bureau of Standards, 1983 'Air Quality Criteria for Storage of Paper Based Archival Records', NBSIR 83-2795, Washington DC: National Bureau of Standards.
- [43] National Bureau of Standards (1983) National Bureau of Standards, 1983. 'Air Quality Criteria for Storage of Paper Based Archival Records', NBSIR 83-2795, Washington DC: National Bureau of Standards.
- [44] EU Air Quality Directive (2008/50/EC).
- [45] WHO (WHO, World Health Organization) (2005) Air Quality guidelines: global update 2005.
- [46] Watson, J.G., Chow, J.C., Lurmann, F.W., Musarra, S. (1994) Ammonium nitrate, nitric acid, and ammonia equilibrium in wintertime Phoenix, Arizona. Journal of the Air & Waste Management Association, 44, 405:412.

